

To: 1 030828
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-21,282-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Operator: Viking Resources
Name & Address: 120 South Market, Suite 518
Wichita, KS 67202-3819

Approx. SE NE, SEC. 8, T 24 S, R 22 W
3080 feet from S section line
440 feet from E section line
Lease Name Charles Fagen Well # 1
County Hodgeman 152.20
Well Total Depth 4683 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White and Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 6 p.m. Day: 13 Month: 7 Year: 19 87

Plugging proposal received from Bob Casper

(company name) White and Ellis Drilling, Inc. (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2370' Anhydrite 1479-1500'

1st plug at base Anhydrite with 50 sx cement, 2nd plug at 800' with 100 sx cement,
3rd plug at 30' below base of surface pipe with 40 sx cement,
4th plug at 0-40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 7:30 p.m. Day: 13 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,

2nd plug at 800' with 100 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. (If additional description is necessary, use BACK of this form.)

I (Steve Quin) observe this plugging. JUL 16 1987

DATE 7-21-87

Signed Steve Quin (TECHNICIAN)

INV. NO. 17546