

1030166

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,138-0000

W/2 W/2 SE, SEC. 9, T 24 S, R 22 W/2

1320 feet from ~~W~~S section line

2510 feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Hall Well # 4

Operator: Viking Resources

County Hodgeman

Name & Address 217 East William

Well Total Depth 4679 152.07 feet

Wichita, KS 67202-4005

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 438

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202-3484

Company to plug at: Hour: 7:00 pm Day: 26 Month: April Year: 19 84

Plugging proposal received from Judy Stejben

(company name) White & Ellis (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1470' with 50 sx cement

2nd plug at 900' with 50 sx cement

3rd plug at 450' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement

Plugging Proposal Received by Steve Dumont (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: Midnight Day: 26 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement, 2nd plug at 900' with

50 sx cement, 3rd plug at 450' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied  
(If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

MAY 03 1984

CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 5-7-84

INV. NO. 1398

4-26

Signed Steve Dumont (TECHNICIAN)