

1 040981. 7-9

API NUMBER 15- 083-21,425 - 0000

STATE CORPORATION COMMISSION
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, KS 67202

PLUGGING SECTION App. SW SE NW, SEC. 19, T 24 S, R 22 W/E

2280 feet from NE section line

1730 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7567

Lease Name Durler Well # 1

Operator: Jack Bowles

County Hodgeman 156.65

Name & Address P.O. Box 3285

Well Total Depth 4820 feet

Edmond, OK 73083-3285

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 395

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 8:15 a.m. Day: 9 Month: 7 Year: 1995

Plugging proposal received from Harvey Moore

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1510-1554'

1st plug at 1554' with 50 sx cement, 2nd plug at 750' with 80 sx cement,

3rd plug at 415' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:45 a.m. Day: 9 Month: 7 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 1554' with 50 sx cement,

2nd plug at 750' with 80 sx cement,

3rd plug at 415' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If you do not observe this plugging.

DATE 7-18-95

INV. NO. 43096

Signed Steve Pfeifer (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION JUL 17 1995