

2 040180

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-095-20937-00-00

C-SE-SW, SEC. 8, T 29 S, R 7 W/E

660 feet from N/S section line

3300 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Lease Name Woolridge Well # 1

Operator: Kansas Petroleum Inc

County Kingman 148.53

Name & Address Jim Tashaff

Well Total Depth 4570 feet

225 N. Market St #310

Conductor Pipe: Size _____ feet

Wichita Ks. 67202

Surface Casing: Size 8 3/8 feet 276

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176 Chase Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Bill

(company name) Kelso Casing Pulling (phone) _____

were: 50sx on Bottom to 3825

4 bulls, 15 gel, 120 ⁶⁰/₁₄₀ 2 1/2 3%

5 1/2 4228' of 1255x Rec. 2600'

Perfs. 4152-66

4-1-85
APR - 1 1985

Plugging Proposal Received by Steve Van Gieson & Ron Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1025 Day: 26 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Kelso moved over hole and set up. Sun Cementing Pumped 50 sacks of ⁶⁰/₁₄₀ Poz-mix Cement to a depth of 3825. As Sun was pulling their wire line out of the hole, the wire broke leaving about 600' of wire in the hole. Kelso fished out the wire and the casing was shot at at 2600' and recovered. The top was plugged by pumping 4 bulls of Hullo, 15 cks of gel & 120 cks of ⁶⁰/₁₄₀ Poz-mix cement thru

Remarks: Sun Cementing # 206193 SI 600# MX 750#

(If additional description is necessary, use BACK of this form.)

INVOICED (Please observe this plugging.)

DATE 4-4-85

Signed Steve Van Gieson
(TECHNICIAN)

INV. NO. 7544

WK

RO