

2 090018

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- -095-21,171-00-00  
C-SENW, SEC. 8, T 29 S, R 7 W/E  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Lease Name Schrag Well # 1

Operator: Kansas Petroleum, Inc.

County Kingman

Name & Address 225 North Market

Well Total Depth 4570 <sup>148.53</sup> feet

Wichita, Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing & Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: \_\_\_\_\_ p.m. Day: 6 Month: 7 Year: 19 84

Plugging proposal received from Kelso--Norman Voth

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: sand back to 4360'--5 sacks--3 hulls 6 Gel--100 sacks

RECEIVED  
STATE CORPORATION COMMISSION

JUL 18 1984  
7-18-84  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:36 p.m. Day: 9 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT The bottom of the hole was filled with sand to 4360' and

5 sacks of cement was spotted on top of sand through the bailer. The pipe was shot off,

and 3304' of 5 1/2" was recovered. The top was plugged by pumping 3 sacks of hulls and

6 sacks of gel and 100 sacks of 50-50 pos 2%GEL, 3% cc cement to surface.

I.S.P. 300

Remarks: Halliburton Ticket #827488  
(If additional description is necessary, use BACK of this form.)

INVOICED (If desired, observe this plugging.)

DATE 7-25-84

Signed David West (TECHNICIAN)

INV. NO. 2638 7-9