

State of Kansas



15-095-300950000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1966
10-21-66

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Red Bishop of Leben Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Martin & Keller

Complete Address: 1035 Kennedy Bldg., Tulsa, Oklahoma

Lease Name: Jones Well No. # 1

Location: C SW NE Sec. 12 Twp. 28 Rge. 5 (E)(W) W

County Kingman Total Depth 3855' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:

214' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent