



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 3, 1969

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-155-20103-0000

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 17 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wassinger of Knight Casing Pulling Co., Inc. as this date requested permission to plug the following described well:

Mr. Wassinger guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie

Complete Address: 412 Union Center, Wichita, Kansas 67202

Lease Name: Graber Well No. 1

Location: C N/2 SE NW Sec. 34 Twp. 23 Rge. 4 (E) (W) X

County: Reno Total Depth 3425' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wassinger was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 5 sacks cement.

Bail hole to 235'. Set rock bridge from 235' to 225' and cement with 35

sacks cement. Fill hole with mud to 40'. Set rock bridge from 40' to 30'

and cap hole with 15 sacks cement.

Very truly yours,


 Conservation Division Agent