

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 25, 1967 AUG 1 1967

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-155-30709-00-01

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Fred J. Ayesch

Complete Address: 438 Wetmore Drive, Wichita, Kansas 67209

Lease Name: Mc Elwain Well No. 1

Location: Nec SE Sec. 34 Twp. 23 Rge. 4 (E) (W) X

County Reno Total Depth 3593' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3550' and cement with 5 sacks.

Fill hole with mud to 310'. Set rock bridge from 310' to 300' and

cement hole with 30 sacks. Fill hole with mud to 35'. Set rock bridge

from 35' to 25' and cap hole with 15 sacks cement.

Very truly yours,

Conservation Division Agent