

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 03 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Engle of Slawson Drlg. has this

date requested permission to plug the following described well:

Mr. Engle guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 200 Douglas Bldg., Wichita, Ks.

Lease Name: Nielson "G" Well No. 1

Location: Appx C' NE Sec. 5 Twp. 24 Rge. (E)(W) 22

County: Hodgeman Total Depth 4735' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Engle was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill
pipe. Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent