

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-083-21,282-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Viking Resources OPERATORS LICENSE NO. 5011

ADDRESS 120 S. Market, Suite 518 PHONE # (316) 262-2502

LEASE (FARM) Charles Fagen WELL NO. 1 WELL LOCATION SE NE COUNTY Hodgeman

SEC. 8 TWP. 24 S RGE. 22 (X) or (W) TOTAL DEPTH 4683' PLUG BACK TD N/A

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8^{5/8}" SET AT 209' CEMENTED WITH 135 SACKS 2% gel
3% cc

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT N/A

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Per K.C.C.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not, explain)

Well log and ACO-1 will be filed by operator.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN as soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dean Calvin PHONE # (316) 792-2424

ADDRESS P.O. Box 1586, Great Bend, Ks. 67530

PLUGGING CONTRACTOR White & Ellis Drilling, Inc. LICENSE NO. 5420

ADDRESS 401 E. Douglas, Suite 500, Wichita, Ks., 67202 PHONE # (316) 263-1102

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Michael L. Conidine
(Operator or Agent)

7-21-87 JUL 21 1987

DATE: July 20, 1987
Wichita, Kansas

85
2N

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date July 15, 1987 month day year

API Number 15-083-21,282-0000

OPERATOR: License # 5011
Name Viking Resources
Address 120 S. Market, Suite 518
City/State/Zip Wichita, KS 67202-3819
Contact Person Jim Devlin
Phone (316) 262-2502

APPROX SE NE Sec. 8 Twp. 24 S, Rg. 22 X West
3080 Ft. from South Line of Section
440 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5420
Name White and Ellis Drilling, Inc.
City/State Wichita, KS

Nearest lease or unit boundary line 440 feet
County Hodgeman

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj X Pool Ext Air Rotary
OWWO Expt Wildcat Cable

Lease Name Charles Fagen Well # 1
Ground surface elevation Unknown 2370 feet MSL

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Domestic well within 330 feet yes X no
Municipal well within one mile yes X no

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 10 June 1987 Signature of Operator or Agent James B. Devlin Title Operator

Depth to bottom of fresh water 200
Depth to bottom of usable water 375

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X
This Authorization Expires 12-16-87 Approved By 6-16-87

Surface pipe by Alternate 1 X
Surface pipe planned to be set 200
Conductor pipe required None

Projected Total Depth 4750 feet
Formation Mississippian

Spud 7-6-87

8 5/8" - 200 +

D.G.

(NO WW)

Approx. SE NE Sec. 8 Twp. 24 S, Rg. 22 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Base Anhydrite feet depth with 40 50 SXS of 60/40 pozmix 670 gal
2nd plug @ 550 800 feet depth with 40 100 SXS of 60/40 pozmix
3rd plug @ 30' below base of surf feet depth with 30 40 SXS of 60/40 pozmix
4th plug @ 0-40 feet depth with 10 SXS of 60/40 pozmix
5th plug @ feet depth with SXS of
(2) Rathole with 15 SXS (b) Mousehole with 10 SXS

PUSHER Bob Casper
TD 4683 FORMATION MISS
SURFACE PIPE 8 5/8" @ 209
ANHYDRITE 1477 ELEVATION 2370
STARTING TIME & DATE 7-13-87 6:00 AM
COMPLETION TIME & DATE 7:30 PM
1st PLUG @ 1500 FT. W/ 50 SX
2nd PLUG @ 800 FT. W/ 100 SX
3rd PLUG @ 240 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SAND SX
CEMENT COMPANY ALLIED
TECHNICIAN S.A.

WITNESSED BY plugging SA
RECEIVED STATE CORPORATION COMMISSION
JUL 16 1987
CONSULTATION DIVISION
Wichita, Kansas
Carroll & Johnson