

WELL PLUGGING RECORD

Give All Information Completely
Make Regular Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Fitting Building
Wichita, Kansas

Reno County, Sec. 34 Twp. 23 Rge. 4 (E) 4 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE SE

Lease Owner Sohio Petroleum Co.

Lease Name McElwain Well No. 4

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 3-30 19 35

Application for plugging filed 8-7 19 50

Application for plugging approved 8-9 19 50

Plugging commenced 10-20 19 50

Plugging completed 10-29 19 50

Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3588 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Hunton Lime		3580	3588	8-5/8"	3580'	3032'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3588' to 3575' - Chat & 8 sacks cement

3575' to 350' - Heavy mud

350' to 300' - Bridge & 25 sacks cement

12' to Cellar - Bridge & 12 sacks cement

11-6-50

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 - 1950
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sohio Petroleum Company
Address Box 671
Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
J. H. Bond (employee of owner) or (owner or operator) of the above-described well,

-being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond

(Address)

SUBSCRIBED AND SWORN to before me this 30th day of October, 19 50.

My Commission Expires July 2, 1953

Russell Miller
Notary Public.

PLUGGING
FILE SEC 34 T 23 R 4W
BOOK PAGE 20 LINE 25

15-155-01485-0000

LOG

Sohio Petroleum Company

McElwain No. 4

<u>Top</u>	<u>Bottom</u>	<u>Formation and Remarks</u>	<u>Casing Record</u>		
0	95	Sand & Gravel	15 1/2"	167'	
95	160	Sandy Shale & Shells	12 1/2"	507' 6"	
160	300	Shale	8 1/4"	8 5/8"	3624'
300	337	Shale & Shells			
337	462	Shale & Shells			
462	733	Shale & Shells			
733	793	Shale			
793	984	Shale & Shells			
984	1069	Shale			
1069	1133	Shale & Lime Shells			
1133	1475	Shale & Shells			
1475	1600	Shale & Shells			
1600	1735	Shale			
1735	1866	Shale & Shells			
1866	1967	Shale			
1967	2058	Broken Lime (Acid Test 2000 O.K.)			
2068	2262	Broken Lime & Sandy Shale			
2262	2374	Broken Lime			
2374	2429	Sand & Lime Shells			
2429	2534	Shale & Shells			
2534	2604	Lime			
2604	2897	Lime			
2897	2910	Shale			
2910	2969	Broken Lime			
2969	3035	Broken Lime & Shale			
3035	3095	Broken Lime			
3095	3198	Shale & Lime Shells			
3198	3247	Shale & Shells			
3247	3250	Shale			
3250	3389	Chat.			
3389	3474	Lime			
3495	3525	Shale & Lime Shells			
3525	3575	Shale			
3572	3584	Core			
3580	3588	Hunton Lime			

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1950

CONS. DIVISION

RECEIVED

Conservation Div.

AUG 9 - 1950

STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
 FILE SEC 34 T 23 R 10
 BOOK PAGE 20 LINE 25