


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 11 Twp. 29S Rge. (E) 6 (W)
Location as "NE/CNWxSWx" or footage from lines SE NW Sec. 11-29S-6W
Lease Owner Beardmore Oil Inc.
Lease Name Hedrick "C" Well No. 1
Office Address 700 - One Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-11 19 69
Application for plugging filed 8-11 19 69
Application for plugging approved 8-11 19 69
Plugging commenced 8-11 19 69
Plugging completed 8-11 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4105 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Beds		0	200'	8-5/8"	200'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

0' to 40' - 10 sacks cement
40' - wood plug
40' to 125' - heavy mud
125' to 200' - 25 sacks cement
200' - wood plug
200' to 4105' - heavy mud
Also: 2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Heber Beardmore ~~owner~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore
700 - 120 Bldg., Wichita, Kansas

13 day of August, 1969

Shirley Ann Jackson
Shirley Ann Jackson Notary Public.

7-13-71



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

HEDRICK #1
 C SE NW Section 11-29S-6W
 Kingman County, Kansas

Commenced: August 1, 1969
 Completed: August 11, 1969

OPERATOR - Beardmore Oil, Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	760	Red bed	Ran 5 joints of 8-5/8" casing, set @ 200' w/175 sacks cement.
760	895	Red bed and shale	
895	1102	Shale and shells	
1102	1137	Anhydrite	
1137	3290	Lime and shale	
3290	3920	Lime	
3920	4015	Lime and shale	
4015	4105	Lime	
4105	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE NW Section 11-29S-6W, Kingman County, Kansas, to the best of my knowledge and belief.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 12 day of August, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
 Barbara J. Layton, Notary Public

