


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Kingman County. Sec. 7 Twp. 29S Rge. (E) 6 (W)  
Location as "NE/CNW/SW" or footage from lines C SE SE  
Lease Owner Pickrell Drilling Company  
Lease Name Kaufman "B" Well No. 1  
Office Address 705 Fourth National Bank Bldg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 28 19 66  
Application for plugging filed June 1 19 66  
Application for plugging approved June 2 19 66  
Plugging commenced June 2 19 66  
Plugging completed June 6 19 66  
Reason for abandonment of well or producing formation Pipe set on gas show, Made too much water to be commercial.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation Mississippi Depth to top 4110 Bottom 4200 Total Depth of Well 4200 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	203'	None
				4 1/2"	4202'	3501'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 25 sacks with pump truck, placed from 3753' to 4446'.  
Set 10' rock bridge at 200', dumped 25 sacks cement, mudded to 40', dumped 10 sacks, filled to surface.

*Handwritten initials and date: RCD, 06-02-66*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Winfield Oil Field Service, Inc.  
Address P. O. Box 952, Winfield, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Dale M. Robinson (owner or operator) of the above-described well being this day before me on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson  
Dale M. Robinson  
705 4th Natl Bank Bldg, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 9th day of June, 19 66

My commission expires May 10, 1970

L. M. Whiting  
L. M. Whiting, Notary Public.



ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY  
705 4th Natl Bank Bldg.  
Wichita, Kansas

Rotary Drilling Commenced 3-21-66  
Rotary Drilling Completed 3-31-66

LOCATION: Kaufman "B" No. 1, C SE SE Section 7-29S-6W, Kingman County, Kansas.

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: 203' (9 jts) 8 5/8" surface casing set with 155 sacks cement.  
Circulated. (135 jts) 4 1/2" casing set at 4196' with 150  
sacks cement. Completed 2:45 A.M. April 1, 1966.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

50	Sand	<u>C. F. S.</u>
203	Red Rock	3325
1040	Red Rock & Shale	3618
2465	Lime & Shale	3630
2745	Shale, Lime, Sandy	3655
3302	Sand & Shale & Lime	3700
3325	Lansing	3733
3505	Lime	3770
3618	Shale & Lime	4130
3793	Lime	4141
4115	Lime & Shale	4150
4200	Mississippian - RTD	4168
		4200

Slope Tests

1500
2500
3500
4000

S. L. M.

2306
3055
3872

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN - 2 1966

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 21th day of April, 1966, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires June 21, 1966

Maxine Blackman  
Maxine Blackman, Notary Public