

Give All Information Completely
Make Receipt of Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD 15-095-30098000

Kingman County. Sec. 19 Twp. 29 Rge. 5 (E) W (W)

Location as "NE/CNW/SW" or footage from lines approx. C SE NW

Lease Owner Tom Kat, Inc.

Lease Name Bentley A Well No. 1

Office Address 1127 Wichita Plaza, Wichita, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed Sept. 9 19 66

Application for plugging filed Sept. 9 19 66

Application for plugging approved Sept. 9 19 66


Plugging commenced Sept. 9 19 66

Plugging completed Sept. 9 19 66

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well Herman Justus

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4465 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	224'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud was put into the hole from 4465' to 200', where the bottom plug was set and cemented with 25 sacks cement. Mud was again put into the hole to a depth of 40', where the top plug was set and cemented with 10 sacks. 2 sacks of cement was put into the rathole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1966

CONSERVATION DIVISION
Wichita, Kansas

09-21-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don G. Calvin (employee of owner) ~~of the above-described well~~, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don G. Calvin

1127 Wichita Plaza, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of September, 1966

My commission expires April 16, 1969

Carolyn L. Scott
Notary Public.

15-095-300980000

DRILLERS LOG

#1 BENTLEY A

TOM KAT, INC.

C SE NW, Sec. 19-29-5W

KINGMAN COUNTY, KANSAS

RECEIVED
STATE COMMISSION
SEP 21 1966
OIL & GAS DIVISION
TOPEKA, KANSAS

Commenced: 8/29/66
Completed: 9/9/66
Elevation: 1511 KB

<u>FROM</u>	<u>TO</u>	
0	220	Red Bed & sand
220	350	Red Bed
350	845	Shale-shells-sand
845	968	Shale & shells
968	995	Anhydrite
995	1250	Shale & lime
1250	2061	Lime & shale
2061	3325	Shale & lime
3325	3495	Lime & shale
3495	3812	Lime
3812	4068	Lime & shale
4068	4115	Cherty Lime
4115	4195	Lime - Chert
4195	4335	Cherty lime
4335	4395	Lime
4395	4440	Lime & shale
4440	4450	Shale
4450	4465	Lime - chert
	4465	Rotary Total Depth

REMARKS:
Set 224' of 8 5/8" surf. casing with 200 sacks cement.

TOPS: (sample)

Heebner 2964 (-1453)
Snyderville sand 3019 (-1508)
Lansing marker 3209(-1698)
Stalnaker sand 3246 (-1735)
K. C. Lime 3496 (-1985)
Mississippian 4068(-2557)
Kinderhook shale 4336 (-2825)
Viola lime 4449 (-2938)

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

Don G. Calvin

Don G. Calvin

STATE OF KANSAS
 SS
COUNTY OF SEDGWICK

Subscribed and sworn to before me this 20th day of September, 1966.

Carolyn L. Scott

Carolyn L. Scott, Notary Public

My Commission Expires: April 16, 1969.