

15095-30012-000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 19 Twp. 29S Rge. (E) 5 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Pickrell Drilling Company
Lease Name Woodard Well No. 1
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 26, 1965
Application for plugging filed March 26, 1965
Application for plugging approved March 26, 1965
Plugging commenced March 26, 1965
Plugging completed March 26, 1965
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4475 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	213'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 216', set plug, cemented with
20 sacks cement. Heavy mud to 40', set plug,
cemented with 10 sacks cement to bottom of
cellar; plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

04-06-65 APR 6 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th National Bank Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of March, 1965

My commission expires June 21, 1966

Maxine Blackman
Notary Public.

ROTARY DRILLING LOG

15-095-30012-0500

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg
Wichita, Kansas

Rotary Drilling Commenced 3-11-65

Rotary Drilling Completed 3-26-65

LOCATION: C NW NW SW Section 19-29-5W, Kingman County, Kansas
WOODARD No. 1

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (10 jts) 8 5/8" surface casing set at 213', cemented with 155 sacks cement. Circulated. Completed 4:00 P.M. March 11, 1965. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Sand & Clay	<u>C. F. S.</u>
213	Red Rock	3215
1015	Shale & Shells	3230
1520	Lime & Shale	3247
1680	Lime	3265
3050	Lime & Shale	3500
3235	Shale & Sand	3530
3355	Lime & Shale	3589
3500	Lime	3598
3565	K.C. Lime	3629
3833	Lime	3666
4045	Lime & Shale	4060
4060	Shale & Chert	4070
4330	Mississippian	4400
4414	Shale & Lime	4406
4425	Kinderhook	4414
4440	Viola	4420
4475	Simpson - RTD	4425
		4430
		4435
		4440
		4445
		4450
		4455
		4475
		<u>Slope Test</u>
		2700
		3200
		3700
		4200
		<u>S. L. M.</u>
		3500
		3922
		4362

RECEIVED
STATE CORPORATION COMMISSION
APR 6 1965
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 31st day of March, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public