


STATE OF KANSAS
CONSERVATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Kingman County, Sec 30 Twp. 29S Rge. NE 5 (W)
Location as "NE/CNWxSWx" or footage from lines SE SE NW



Locate well correctly on above
Section Plat

Lease Owner Texaco Inc.
Lease Name B. J. Stucky Well No. 1
Office Address 614 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 9-7-1954
Application for plugging filed 11-1-1968
Application for plugging approved 11-4-1968
Plugging commenced 11-12-1968
Plugging completed 11-22-1968
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 7-10-1968
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren
Producing formation Simpson Depth to top 4461 Bottom 4468 Total Depth of Well 4468 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Simpson	Oil	4461	4468	10-3/4"	442'	None
				7"	4455'	3766'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged as follows: 4468-28 w/sand
4428-08 w/10 sxs cmt
4408-400 w/mud & wtr
400-390 w/rock
390-300 w/35 sxs cmt
300-40 w/mud
40-30 w/rock
30-surf w/15 sxs cmt
Comp 12 Noon 11-22-68

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
M. R. Wilson (employee of owner) or (owner of operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. R. Wilson
614 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of December, 1968



Peggy Sue Jones
Notary Public.

The Texas Company
Tulsa, Oklahoma

Tulsa, Oklahoma
August 30, 1954

Contractor: Stickle Drilling company
Drilling commenced: August 2, 1954
Drilling completed: August 21, 1954

B. J. Stucky #1 SE-SE-NW- Section 30-29S-5W- Kingman Co., Kansas

DRILLERS LOG

Sand & Red Bed	0-100
Shale & Shells	100-1140
Lime	1140-1585
Lime & Shale	1585-1730
Shale & Shells	1730-2065
Shale & Lime	2065-2245
Shale & Shells	2245-2365
Shale & Lime	2365-2570
Lime & Shale	2570-2660
Shale & Lime	2660-2880
Lime & Shale	2880-3116
Sandy Shale	3116-3225
Sandy Lime & Shale	3225-3325
Lime	3325-3367
Lime & Shale	3367-3520
Lime	3520-3724
Lime & Shale	3724-4029
Shale & Lime	4029-4122
Chat	4122-4202
Lime	4202-4355
Lime & Shale	4355-4395
Shale	4395-4468 TD

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1968
CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete drillers log of The Texas Company's B. J. Stucky #1 SE-SE-NW Section 30-29S-5W- Kingman County, Kansas.

Fred E. Stickle
Fred E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956
My commission expires