


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 30 Twp. 29 Rge. (E) 5 (W)
Location as "NE/CNWxSWx" or footage from lines 75' E' SW SW NE
Lease Owner Robert F. Vinson
Lease Name Graber Twin Well No. 1
Office Address 2209 Miramar, Wichita Falls, Texas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced February 27 19 68
Plugging completed March 4 19 68
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Flying
Producing formation Depth to top Bottom Total Depth of Well 4462' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	281'	none
				5-1/2"	4458'	3854.46'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4462' - 4400' - sand
4400' - 4360' - 5 sacks cement
4360' - 265' - mud
265' - 255' - rock bridge
255' - 180' - 25 sacks cement
180' - 40' - mud
40' - 30' - rock bridge
30' - base - 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.,
Address S P. O. Box 562, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. T. L. Nutt

(Signature) P. O. BOX 562, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of March 19 68

My commission expires July 31, 1970

Mary M. Guernier
Notary Public.

15-095-200540000

ROTARY DRILLING LOG

Operator: Rains & Williamson
Oil Co., Inc.
** #1 GRABER,
75' East of SW SW NE 30-29S-5W
Kingman County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 11-25-67
Completed: 12-7-67 (Rotary)

Remarks: Set 8-5/8" surface casing at 281' w/215 sacks GL-3.

** Operations were assumed at casing point by Robert E. Vinson
4726 Jacksboro Highway
Wichita Falls, Texas

Set 5-1/2" casing at 4458' w/100 sacks salt saturated 50-50 pozmix.

Formations

Sand	40'
Red Bed	282'
Shale	928'
Shale and Lime	1550'
Lime and Shale	1754'
Shale	2080'
Shale and Lime	2610'
Lime and Shale	3390'
Shale	3519'
Lime and Shale Breaks	3555'
Lime and Shale	3600'
Lime	3742'
Lime and Shale	3828'
Lime	3950'
Lime and Shale	4205'
Lime	4350'
Lime and Shale	4440'
Lime	4460'
Rotary Total Depth	4460'

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 13th day of December, 1967.



Sherry Gish
Sherry Gish Notary Public

My Commission Expires:
June 30, 1971