

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

15-095-20656-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 16 Twp. 29S Rge. 8W ~~8W~~
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NE SW NE

Lease Owner Keener Oil Company
Lease Name J. Walter Clouse Well No. 1
Office Address 406 Nat'l. Bank of Tulsa Bldg. Tulsa,
Character of Well (Completed as Oil, Gas or Dry Hole) 74103
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed November 26, 19 77
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced November 26, 19 77
Plugging completed November 26, 19 77
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,220
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled hole with heavy rotary mud from 4,220 ft. (rotary total depth) to
210 ft. Set plug at 210 ft. and cemented with 35 sacks cement. Filled
hole with heavy rotary mud from 210 ft. to 40 ft. Set solid plug at 40
ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing
pump truck through 4 1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

DEC 01 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services CONSERVATION DIVISION
410 Union Center Bldg., Wichita, Kansas 67202 Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (employee of owner) ~~owner or operator~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main Wichita, Kansas 67202
(Address)

Elsie Willison
Elsie Willison - Notary Public.

SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 77

My commission expires June 30, 1978



API# 15-095-20,656

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Keener Oil Company**

SEC. **16** T. **29S** R. **8W**
 LOC. **NE SW NE**

FARM **J. Walter Clouse** NO. **1**

COUNTY **Kingman**

TOTAL DEPTH **4,220'**


COMM. **November 18, 1977**

COMP. **November 26, 1977**

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED **November 30, 1977**



CASING

20	10		
15		8-5/8" 205' cemented w/200 sxs cement	ELEVATION 1,643' K.B.
12		6	
13		5	

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	30'
Shale, Sand, and Red Bed	211'
Red Bed and Shale	1,080'
Shale and Lime	1,780'
Lime and Shale	4,180'
Chert	4,220'
Rotary Total Depth	4,220'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting


 Dean Britting

State of Kansas }
 County of Sedgwick } ss:

Suscribed and Sworn to before me a Notary Public
 in and for said county and state this 30th day
 of November, 1977.

Elsie Willison

 Elsie Willison - Notary Public



My Commission Expires:
June 30, 1978

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 01 1977
 CONSERVATION DIVISION
 Wichita, Kansas