


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Form CP-4
15-095-20001-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 17 Twp. 29S Rge. 8W (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Leben Drilling, Inc. etal
Lease Name Bock Well No. 1
Office Address Box 486, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-16-67 19
Application for plugging filed 1-16-67 19
Application for plugging approved 1-16-67 19
Plugging commenced 1-16-67 19
Plugging completed 1-16-67 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	208'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 200', made bridge with cement, hulls and plug and added 25 sacks cement.

Filled with mud to 40', made bridge with hulls, cement, plug and added 10 sacks cement. 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 67

Ulanda Nichols
Notary Public.

My commission expires April 1, 1967

Ulanda Nichols

DRILLER'S LOG

AP

COMPANY: Leben Drilling, Inc. etal
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: BOCK #1
 LOCATION: C SW NE SEC. 17-29S-8W
 KINGMAN COUNTY, KANSAS
 COMMENCED: 1-6-67
 COMPLETED: 1-16-67

0	55	Soil, Clay
55	60	Sand
60	100	Shale
100	208	Redbed, Shale
208	1165	Redbed
1165	1275	Shale, Shells
1275	1600	Shale, Lime, Shells
1600	1840	Lime
1840	2035	Lime, Shale
2035	2405	Shale, Lime, Shale
2405	2610	Lime, Shale
2610	2860	Shale, Lime
2860	3312	Lime
3312	3497	Shale, Sand
3497	3765	Lime
3765	4065	Lime, Shale
4065	4185	Shale, Lime
4185	4200	Lime
4200	4273	Chert
4273	4332	Lime
4332	4350	Lime, Chert
4350	4397	Shale, Lime
4397	4489	Lime, Shale
4489	4517	Viola Lime
4517	4560	Lime
	<u>4560</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 18 1967
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" used surface casing set @ 208' cemented with 150 sacks of Common cement with 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Bock #1 Well, located C SW NE of Section 17, Township 29 South, Range 8 West, Kingman County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
 COUNTY OF BARTON) SS

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 17th day of January, 1967.

[Handwritten signature]

Ulanda Nichols
 Ulanda Nichols

My Commission Expires
 April 1, 1967