


15-095-20331-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Kingman County, Sec. 18 Twp. 29S Rge. 8 (W) 8 (W)  
Location as "NE/CNW/SW" or footage from lines C NE SW  
Lease Owner Lancer Petroleum  
Lease Name Creighton Well No. 1  
Office Address P. O. Box 564, Liberal, Kansas 67901  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 20, 1974  
Application for plugging filed February 20, 1974  
Application for plugging approved February 20, 1974  
Plugging commenced February 20, 1974  
Plugging completed February 20, 1974  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4185' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 200'. Followed by wooden plug, 1/2 sack hulls and 25 sacks cement. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
15-095-20331-0000

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Betty Brandt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt  
505 Union Center, Wichita, Kansas 67202  
(Address)

Subscribed and Sworn to before me this 1st day of March, 1974

My commission expires  
MERCEDES DOBBINS  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Commission Expires  
February 11, 1976



Mercedes Dobbins  
Mercedes Dobbins Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Lancer Petroleum DRILLING COMMENCED: February 12, 1974  
P. O. Box 564  
Liberal, Kansas 67901

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: February 20, 1974  
505 Union Center  
Wichita, Kansas 67202

CASING RECORD: 5 Jts. 206' 8-5/8" LOCATION: Creighton No. 1  
cemented with 200 sacks. C NE SW  
Section 18-29S-8W  
Kingman County, Kansas

0 - 60 Sand & shale  
60 - 160 Red bed  
160 - 207 Red bed & shale  
207 - 555 Red bed  
555 - 1350 Shale & shells  
1350 - 1616 Shale & lime  
1616 - 1630 Shale  
1630 - 1920 Lime  
1920 - 2034 Lime & shale  
2034 - 2912 Shale & lime  
2912 - 3205 Lime  
3205 - 3655 Lime & shale  
3655 - 3772 Lime  
3772 - 4072 Lime & shale  
4072 - 4185 Lime  
4185 Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas


I hereby certify the foregoing statement to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Petty Perrell  
Secretary-Treasurer

STATE OF KANSAS )  
) ss.  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 1st of March, 1974.



Mercedes Dobbins