


15-095-20466-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 18 Twp. 29 Rge. 8-W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines _____
1980 FSL - 1980 FEL
Lease Owner Texas Oiland Gas Corporation
Lease Name Thimesch Well No. 1
Office Address Suite 300 - 200 W. Douglas-Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Gas
Date Well completed 3-28 1976
Application for plugging filed 12-8 1981
Application for plugging approved 12-10 1981
Plugging commenced 2-1 1982
Plugging completed 2-15 1982
Reason for abandonment of well or producing formation _____

Dry
If a producing well is abandoned, date of last production _____
19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 479
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 3/8	250	None
				4 1/2	4100	2211

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back at 2,600
Sand from 2,600 to 2,530
4 sacks cement 2,530 to 2,500
Ripped at 2,211. Pulled 4 1/2"
Allied pumped in 15 jell - 6 hull - 10 jell
150 sacks common cement - 3% C. C.

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1982
RCW
02-19-82
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.
Elmo R. Marguatern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmo R. Marguatern
Medford, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of February, 1982

Jessie Hamilton
Notary Public.

My commission expires April 4, 1982.

WELL LOG

THINTSCH #1
1980' FSL & 1890' FEL
Section 18-29S-8W
Kingman County, Kansas


OPERATOR: TEXAS OIL & GAS CORP. COMMENCED: 3-19-76
CONTRACTOR: XPLOR DRILLING CO. COMPLETED: 3-28-76

CASING RECORD: Ran intermediate casing, cut 256' - 12 1/2" hole.
Ran 6 joints of used 24" 8 5/8" casing, set at
250'. Cement with 250 sacks common cement, 2%
gel. 3% cal. chloride.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Soil & Sand	0	80	1667 Gr.
Red Bed	80	259	1672 D.F.
Shale	259	540	1675 K.B.
Red Bed & Shale	540	1103	
Anhydrite	1103	1106	
Lime & Shale	1106	1670	
Shale	1670	1980	
Shale & Lime	1980	4179	
R.T.D.	4179		

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I certify that this is a true and correct copy of the Driller's Log of
the well drilled 1980' FSL & 1890' FEL of Section 18-29S-8W, Kingman
County, Kansas, to the best of my knowledge and belief.



RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1981
CONSERVATION DIVISION
Wichita, Kansas

Wayne L. Kirkman
Wayne L. Kirkman, Owner

Subscribed and sworn to before me this 31st. day of March 1976.

MY COMMISSION EXPIRES:
August 25, 1976

Virginia Lee Smith
Virginia Lee Smith, Notary Public