

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-095-21081-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kingman County, Sec. 19 Twp. 29S Rge. 8W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
330 ENL 2310 FWL

Lease Owner Texas Oil & Gas Corp.  
Lease Name Youngers Well No. A-1  
Office Address Suite 300-200 W. Douglas, Wichita, Kansas 67201  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above Section Plat

Dry  
Date Well completed 4-18 1981  
Application for plugging filed Oct 22 1981  
Application for plugging approved Oct 25 1981  
Plugging commenced 2-15 1982  
Plugging completed 2-23 1982  
Reason for abandonment of well or producing formation  
Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2600'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	297	None
				4 1/2"	2598	1922

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug back at 2568'  
Dumped sand from 2568' to 2475'  
4 sacks cement from 2475' to 2430'  
Ripped 2200 - 2100' - 1922'  
Allied pump in 15 Gell, 6 Hull, 10 Gell  
150 sacks common cement 3% c.c.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 26 1982

CONSERVATION DIVISION  
Wichita, Kansas

rcvd  
02-26-82

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.  
Elmer R. Marguaster (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer R. Marguaster  
Medicine Park, KS.  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of February, 1982

Jessie Hamilton  
Notary Public.

My commission expires April 4, 1982

DRILLERS LOG

OPERATOR: Texas Oil & Gas Corp., Inc.  
200 West Douglas  
Wichita, Kansas 67202

WELL NAME: #1 Youngers 'A'  
NE NE NW Sec. 19-29S-8W  
Kingman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
200 Douglas Building  
Wichita, Kansas 67202

COMMENCED: 4/13/81

COMPLETED: 4/17/81

RTD: 2600'

SURFACE CASING: 8-5/8" set at 297 with 275 sx

PRODUCTION CASING: 4-1/2" set at 2598' with 150 sx

0' to 300' Red Bed  
300' to 1350' Shale  
1350' to 2440' Lime & Shale  
2440' to 2600' Tarkio  
RTD 2600'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the #1 Youngers 'A' log for Texas Oil & Gas Corp.

*James C. Remsberg*  
James C. Remsberg

Subscribed and sworn to me this  
30th day of April, 1981

*Mary Lou Taylor*  
Mary Lou Taylor, Notary

My commission expires January 17, 1985

PROD. FILE

RECEIVED  
STATE CORPORATION COMMISSION

OCT 2 1981  
CONSERVATION DIVISION  
Wichita, Kansas

