

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Kingman County, Sec. 20 Twp. 29S Rge. 8W (E) W (W)
Location as "NE/CNW%SW%" or footage from lines SW NW NE
Lease Owner Pet-Ex
Lease Name Ellis Well No. 1
Office Address 705 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed May 14 19 62
Application for plugging filed May 14 19 62
Application for plugging approved May 14 19 62
Plugging commenced May 14 19 62
Plugging completed May 14 19 62
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Depth to top Bottom Total Depth of Well 4565 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	295'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug hole w/mud to 270'
1/2 sx hulls, plug 20 sx
cement, mud to 40' 1/2 sx
hulls, plug 10 sx cement,
2 sx in rathole

RECEIVED
PCD STATE CORPORATION COMMISSION
06-13-62 JUN 13 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
George A. Angle (explorer or owner) (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of May, 19 62

Notary Public

My commission expires 11-17-62



DRILLERS LOG

Well No. 1

CASING RECORD:	COMPANY:	Pet-Ex	DESCRIPTION:	SW NW NE
8 5/8" @ 295'	CONTRACTOR:	Red Tiger Drilling Co.	20-298-SW	Kingman Co.,
w/225 ex cement	COMMENCED:	May 1, 1962	Kansas	
	COMPLETED:	May 14, 1962	ELEVATION:	1680 BF
				1683 RB
TOTAL DEPTH: 4366'				

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Soil & Sand	0	20	
Clay	20	65	
Sand & Clay	65	90	
Redbed	90	243	
Redbed, Rock & Shale	243	490	
Shale & Shells	490	1316	
Anhydrite	1316	1342	
Shale & Shells	1342	1400	
Lime & Shale	1400	3065	
Lime	3065	3286	
Heebner	3286	3290	
Lime & Shale	3290	3300	
Sandy Lime & Shale	3300	3413	
Sandy Shale	3413	3510	
Sandy Lime & Shale	3510	3515	
Lime	3515	3955	
Lime & Shale	3955	4007	
Lime	4007	4085	
Lime & Shale	4085	4213	
Miss Chert	4213	4303	
Miss Lime	4303	4325	
Miss Lime & Chert	4325	4415	
Lime & Shale	4415	4489	
Shale	4489	4500	
Lime & Shale	4500	4502	
Lime & Chert	4502	4545	
Simpson Sand	4545	4566	

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1962
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angelo
George A. Angelo

Subscribed and sworn to before me this 15th day of May, 1962.

Mapine Head
Notary Public

My Commission Expires:

11-17-62