

WELL PLUGGING RECORD

Kingman County. Sec. 20 Twp. 29S Rge. 8W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW/4 NW/4 SE/4

Lease Owner Gear Petroleum Company, Inc.
Lease Name Clouse "F" Well No. 1
Office Address 300 Sutton Place, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

D & A

Date Well completed	April 22,	1981
Application for plugging filed	April 22,	1981
Application for plugging approved	April 22,	1981
Plugging commenced	April 22,	1981
Plugging completed	April 22,	1981

D & A

If a producing well is abandoned, date of last production _____ 19:_____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 14,220
Show depth and thickness of all water, oil and gas formations. _____

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	195'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole @ 250' w/60 sx cement
@ 40' w/plug, 1/2 sx hulls, & 15 sx cement
10 sx cement in rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
1720 KSB Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss. Gloria Fawcett contractor
(employee of ~~owner~~ ~~owner's cooperation~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Gloria Sawett
1720 KSB Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1981.

My commission expires

Notary Public.

APR 30 1981
04-30-81
CONSENT DIVISION
Wichita, Kansas



DRILLERS LOG

No. 1 Clouse "F"

CASING RECORD: 8 5/8" @ 203.40' w/180 sx cement
D & A
TOTAL DEPTH: 4,220'

COMPANY: Gear Petroleum Company, Inc.
CONTRACTOR: Red Tiger Drilling Company
COMMENCED: April 15, 1981
COMPLETED: April 22, 1981

DESCRIPTION: SW/4 NW/4 SE/4
Sec. 20-T29S-R8W
Kingman County, Kansas
ELEVATION: 1,649' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	210	
Red Bed	210	713	
Gray Shale	713	1300	
Shale	1300	1700	
Lime	1700	1925	
Lime & Shale	1925	2440	
Shale & Sand	2440	2530	
Shale & Lime	2530	2640	
Lime & Shale	2640	3180	
Shale & Lime	3180	3484	
Lime	3484	3815	
Lime w/Shale	3815	3970	
Lime	3970	4201	
Mississippi	4201	4220	
RTD		4220	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 28th day of April, 1981.

Joyce A. Baer
Notary Public
RECEIVED
STATE COMMISSION COMMISSION

APR 30 1981

CONSERVATION DIVISION
Wichita, Kansas

