

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County. Sec. 23 Twp. 29 Rge. 8 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C S/2 SE SE

Lease Owner Prime Drilling Company

Lease Name Duckworth Well No. 1

Office Address 814-16 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 15 19 57

Application for plugging filed March 15 19 57

Application for plugging approved March 15 19 57


Plugging commenced March 15 19 57

Plugging completed March 15 19 57

Reason for abandonment of well or producing formation oil in commercial quantities not found

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee (M. A. Rives)

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4309 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	261'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 250'. Set Plug #1 at 250' cemented with 1/3 sack Hulls, 20 sacks cement. Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2 at 35' cemented with 1/3 sack Hulls, 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 814-16 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.  
R. R. McNicol (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol  
814-16 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of March, 19 57

My commission expires September 30, 1959

Darlene May  
Notary Public.  
STATE CORPORATION COM.

PLUGGING  
FILE SEC 23 T 29 R 8W  
BOOK PAGE 148 LINE 45

MAR 20 1957  
03-20-57  
CONSERVATION DIVISION  
Wichita, Kansas

ROTARY DRILLING LOG

OPERATOR: Prime Drilling Company  
 Duckworth No. 1  
 C S/2 SE SE Sec. 23-29-8W,  
 Kingman County, Kansas

CONTRACTOR: Prime Drilling Company  
 COMM: 3/1/57  
 COMP: 3/15/57

Remarks: Set 8-5/8" surface casing at  
 261' cemented with 200 sacks Pozmix,  
 2% C.C.

Formations:

Surface Clay & Rock	40'
Red Bed	140'
Red Bed & Red Rock	262'
Red Bed & Shells	580'
Shale & Shells	1080'
Anhydrite	1120'
Shale & Salt	1230'
Shale & Lime	1590'
Lime -Sandy Streaks	1650'
Sandy Lime & Shale	1790'
Lime & Shale	1905'
Lime w/ Shale Streaks	2200'
Shale & Lime	2575'
Shale & Lime Streaks	2725'
Lime & Shale	3005'
Lime w/Shale Streaks	3115'
Lime	3145'
Sandy Lime & Shale	3210'
Lime & Shale	3265'
Sandy Lime & Shale	3445'
Lime	3535'
Lime w/Shale Streaks	3595'
Lime	4125'
Shale & Lime	4190'
Lime & Chat	4234'
Chat	4264'
Lime	4309'
Rotary Total Depth (D&A)	4309'

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

R. R. McNicol  
 R. R. McNicol - Assistant Secretary  
 PRIME DRILLING COMPANY

Subscribed and sworn to before me this 19th day of March, 1957.

My Commission Expires:  
 Sept. 30, 1959.

Darlene May  
 Darlene May - Notary Public

PLUGGING  
 FILE SEC 23 T 29 R 8W  
 BOOK PAGE 148 LINE 45

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 20 1957  
 CONSERVATION DIVISION  
 Topeka, Kansas