

API NUMBER 15-095-20,409 0000

LEASE NAME Iantha Young

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 23 TWP. 29 SRGE. 8 (E) or (W)

COUNTY Kingman

Date Well Completed Aug. 1976

Plugging Commenced 4-6-94

Plugging Completed 4-6-94

LEASE OPERATOR Messenger Petroleum, Inc

ADDRESS Rt. 1 Box 172-A1 Kingman, KS 67068

PHONE#(316) 532-5400 OPERATORS LICENSE NO. 4706

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 03-31-94 permit # 15-095-20409 W (date)  
 by KCC Dist. #2 David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? it was attached to CP-1

Producing Formation Mississippian Depth to Top 4206 Bottom 4254 T.D. 4315

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Mississippian Chert</u>	<u>gas, oil &amp; salt water</u>	<u>4206</u>				
	<u>4206 - 4254</u>	<u>Surface</u>	<u>273</u>	<u>8 5/8</u>	<u>w/250sx</u>	
		<u>Surface</u>	<u>4315</u>	<u>5 1/2</u>	<u>w/200sx</u>	<u>2620'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Sand in to 4148, pour 5 sx common cement, spot 35 sx (60/40 poz w/4% gel) @ 1199.94,  
Spot 35 sx (60/40 poz w/4% gel) @ 777.43, circ from 344.86 to surface w/95 sx  
(60/40 poz w/4% gel), top off w/ 15 sx (60/40 poz w/4% gel), dropped 32', fill to surface  
with common

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address 611 N. Blaine Attica, KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Messenger Petroleum, Inc

STATE OF Kansas COUNTY OF Kingman, ss.

Jon F. Messenger (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jon F. Messenger

(Address) Rt. 1 Box 172-A1 Kingman, KS 67068

SUBSCRIBED AND SWORN TO before me this 28th day of April, 19 94

Mary E. Blumankhoust  
 MARY E. BLUMANKHOUST, Notary Public  
 NOTARY PUBLIC

My Commission Expires: \_\_\_\_\_

STATE OF KANSAS  
 My Appt. Exp. 3-20-98

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 29 1994  
 04-29-94  
 CONSERVATION DIVISION  
 Wichita, Kansas