

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH

		X	

Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 26 Twp. 24S Rge. (E) 22 (W)  
Location as "NE/CNW/SE" or footage from lines. C NW NE  
Lease Owner Sunray DX Oil Company  
Lease Name John Habiger Well No. 1  
Office Address 321 West Douglas, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed September 11, 19 63  
Application for plugging approved September 11, 19 63  
Plugging commenced September 10, 19 63  
Plugging completed September 10, 19 63  
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott, Sublette, Kansas  
Producing formation Non-Producing Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4962 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topeka	Water	3596	3986	8-5/8"	261'	0'
Heebner	Water	3986	3991			
Toronto	Water	4008	4080			
Lsg. K.C.	Water	4089	4392			
Marmaton	Water	4487	4622			
Cherokee Shale	Water	4622	4626			
Cherty Conglomerate	Water	4698	4725			
Mississippi	Water	4725	4962			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud from total depth to 600' and placed 25 sacks cement. Filled with mud to 270' and placed wood plug and 25 sacks of cement. Filled with mud to 40' and placed wood plug, 1/2 sack hulls and 15 sacks cement to surface. Well plugged and abandoned 9-10-63.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company  
Address 1100 Bittling Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
GARY W. PIERCE (employee of owner) OR (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary W. Pierce  
321 W. Douglas, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 63

My commission expires March 22, 1967  
Marjorie P. Joyner Notary Public.

Attachment: Driller's Formation Log.

Sunray DX Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
September 12, 1963

Contractor: Stickle Drilling Company  
Date Commenced: August 27, 1963  
Date Completed: September 9, 1963

John Habiger No. 1  
NW NE Section 26-24S-22W  
Hodgeman County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Lime	274
Shale	600
Shale and shells	1462
Anhydrite	1500
Shale and shells	1749
Shale	2480
Shale and lime	2634
Lime and shale	2890
Shale and lime	3077
Lime and shale	3220
Shale and lime	3581
Lime and shale	4110
Lime	4295
Sand lime	4410
Lime	4520
Lime and shale	4551
Lime	4673
Lime and chert	4735
Lime	4750
Lime and chert	4777
Cherty lime	4842
Lime and chert	4926
Cherty lime	4962 TD
TD Corrected by Electric Log	4968

RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1963  
CONSERVATION DIVISION  
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray DX Oil Company's John Habiger No. 1 Well, NW NE of Section 26-24S-22W, Hodgeman County, Kansas:

*Fred E. Stickle*  
FRED E. STICKLE

*W. Mensley*  
Notary Public

My Commission Expires January 11, 1967.