

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

15-083-20730-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Hodgeman SEC. 29 TWP. 24s RGE. 22w E/W  
 Location as in quarters or footage from lines:  
SW SW SW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Beren Corporation  
 Lease Name Gerritzen #1 Well No. \_\_\_\_\_  
 Office Address 970 Fourth Financial Center, Wichita, Ks 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 11/16/82  
 Plugging completed 11/18/82  
 Reason for abandonment of well or producing formation \_\_\_\_\_  
Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4780'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	565'	none
				4 1/2"	4779'	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 4700' & 4 sacks cement. Shot at  
2850' & 2700', pulled total of 87 joints. Plugged hole with 3 sacks  
hulls, 15 sacks gel, 70 sacks cement, 1 sack hulls, & 15 sacks gel.  
Released plug & displaced with 130 sacks cement.  
Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.


(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November 1982

My Commission expires:



COPY



## WELL LOG

Gerritzen #1  
 SW SW SW Sec. 29-24S-22W  
 Hodgeman County, KS

NAME OF OPERATOR: Beren Corporation  
 970 Fourth Financial Center  
 Wichita, KS 67202

DATE COMPLETED: 10-9-80

FROM	TO	
0	435	Rock, Shale & Sand
435	766	Shale
766	1015	Shale & Red Bed
1015	1111	Sand
1111	2110	Shale
2110	2690	Shale & Lime
2690	2909	Shale
2909	4010	Shale & Lime
4010	4152	Lime
4152	4475	Lime & Shale
4475	4680	Lime
4680	4725	Lime & Shale
4725	4780	Lime
4780		T.D.


STATE OF KANSAS

COUNTY OF BARTON ss

George E. Miller, Jr., President of Blue Goose Drilling Co., Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

*George E. Miller, Jr.*  
 George E. Miller, Jr.

Subscribed and sworn before me this 16th day of October, 1980.



*Helen C. Standley*  
 Notary Public

My Commission Expires: 12-8-83

RECEIVED  
 STATE CORPORATIONAL COMMISSION

NOV 09 1982  
 CONSERVATION DIVISION  
 Wichita Kansas