

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 12/14/82
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API NUMBER 15-083-21,277-0060 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Robert Schulein OPERATORS LICENSE NO. 6785
811 Denver Center Building
ADDRESS 1776 Lincoln Street, Denver, Colorado 80203 PHONE # (303) 839-5495

LEASE (FARM NAME) Downey WELL NO. 16-29

WELL LOCATION C SE/4 SE/4 SEC. 29 TWP. 24S RGE. 22W (E) or (W)

COUNTY Hodgeman TOTAL DEPTH 4,800 FIELD NAME _____

check one:

OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A XX

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes (enclosed)
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN May 21, 1987 @ 6:00 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Macklin Armstrong ADDRESS 2503 Carlsbad Circle, Wichita, KS 67215
PHONE # (316) 722-5141

PLUGGING CONTRACTOR Red Tiger Drilling Company LICENSE NO. 5302

ADDRESS 1720 KSB Building, Wichita, Kansas 67202 PHONE # (316) 263-2371

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Robert Schulein, 811 Denver Center Building,

ADDRESS 1776 Lincoln Street, Denver, Colorado 80203 PHONE # (303) 839-5495

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OR ACTING AGENT.

SIGNED: Robert Schulein
(Applicant or Acting Agent) Robert Schulein
STATE CORPORATION COMMISSION

DATE: June 1, 1987

JUN 3 1987

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 5 17 1987 month day year

API Number 15- 083-21,277-6000

OPERATOR: License # 6785 Name Robert Schulein Address 1776 Lincoln St., #811 City/State/Zip Denver, Colorado 80203 Contact Person Robert Schulein Phone (303) 839-5495

C. SE. SE. Sec. 29. Twp. 24. S. Rg. 22. X West 660 Ft. from South Line of Section 660 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302 Name Red Tiger Drilling Co. City/State Wichita, Kansas 67202 Well Drilled For: Well Class: Type Equipment: XX Oil SWD Infield XX Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 660 feet County Hodgeman Lease Name Downey Well # 16-29 Ground surface elevation 2380 feet MSL Domestic well within 330 feet yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 240' Depth to bottom of usable water 400' Surface pipe planned to be set 400' Projected Total Depth 4850 feet Formation Mississippian

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon testing production casing.

Date April 16, 1987 Signature of Operator or Agent Title Owner/Operator

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 400 feet per Alt. This Authorization Expires 10-10-87 Approved By 4-20-87

Spud 5-13-87 400+ of 8 5/8"

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Anhydrite Base 750' feet depth with 50 80 sxs of 50-50 poz, 6% gel 2nd plug @ 440' feet depth with 40 sxs of 50-50 poz, 6% gel 3rd plug @ 40' feet depth with 10 sxs of 50-50 poz, 6% gel 4th plug @ feet depth with sxs of 5th plug @ feet depth with sxs of (2) Rathole with sxs (b) Mousehole with sxs

PUSHER Boss Crawford TD 4800' FORMATION MISS. SURFACE PIPE 8 5/8" @ 430' ANHYDRITE 1495' ELEVATION 2380' STARTING TIME & DATE 7:40 AM 5-21-87 COMPLETION TIME & DATE 8:50 AM 5-21-87 1st PLUG @ 1540 FT. W/ 50 SX 2nd PLUG @ 750 FT. W/ 80 SX 3rd PLUG @ 440 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Allied TECHNICIAN Dan Goodrow 60/40 poz. 6% gel

RECEIVED STATE CORPORATION COMMISSION MAY 26 1987 CONSERVATION DIVISION Wichita, Kansas