

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23034-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 18-33S-7E
330 feet from N Section Line, 300 feet from W Section Line
Lease Name: LOVE RADCLIFF Well #: 1
County: COWLEY Total Vertical Depth: 2785 feet

Operator License No.: 3910
Op Name: HALE, L.D.
Address: 15000 E TIMBER LAKE RD
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2500		
PROD	5.5	2743		75 SX
SURF	8.625	213		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2016 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: LD HALE Company: LD HALE Phone: (316) 733-5590

Proposed Plugging Method: PER KCC INSTRUCTIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2016 5:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) RUN IN HOLE W / 1" TUBING TO APPROX 2475'. 2) PUMP GEL SPACER, THEN PUMP 14 SKS CLASS A CEMENT (NO BLEND). 3) PULL TUBING OUT OF HOLE, RAN IN WIRELINE AND PERFORATED TUBING TO APPROX. 350', FLUID IN 5.5" CASING DROPPED, BACKSIDE PRESSURED OUT. 4) WAIT 1 HOUR, RAN IN W/ WIRELINE AND TAGGED PLUG AT 2243'. 5) RAN IN TUBING TO APPROX. 350' AND PUMPED APPROX. 100 SKS CLASS A CEMENT (NO BLEND). CEMENT CIRCULATED ON BACKSIDE. CREW OUT OF CEMENT. 6) PULLED TUBING, CEMENT SET FOR APPROX. 1.5 HOURS, RAN TUBING BACK IN AND TAGGED PLUG AT APPROX 90'. PUMPED CEMENT, CIRCULATED TO SURFACE.

* (4) sks tot=1

Perfs:

Top	Bot	Thru	Comments
2693	2699	CSG	
2382	2386	CSG	

Remarks: PERFORATING AND CEMENTING COMPLETED BY ELMORE'S INC. SEDAN, KS. TICKET #: 12208

Plugged through: TBG

District: 02

KCC WICHITA Signed Jonathan Hill
JUN 02 2016 (TECHNICIAN)
RECEIVED

NO
6-9-16