

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-22724-00-00
Spot: SENENE Sec/Twnshp/Rge: 18-33S-7E
990 feet from N Section Line, 330 feet from E Section Line
Lease Name: LOVE Well #: 1
County: COWLEY Total Vertical Depth: 2785 feet

Operator License No.: 3910
Op Name: HALE, L.D.
Address: 15000 E TIMBER LAKE RD
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2784		100 SX
SURF	8.625	205		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2016 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: LD HALE Company: LD HALE Phone: (316) 733-5590

Proposed Plugging Method: PER KCC INSTRUCTIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/20/2016 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

5/18/2016 - 1) RUN 1" TUBING TO APPROX 2700', PUMP GEL SPACER. 2) PUMP 7 SXS CLASS A CEMENT (NO BLEND). 3) PULL TUBING OUT OF HOLE, WAIT 1 HOUR RAN IN WIRELINE AND TAGGED PLUG AT APPROX. 2620'. 4) RUN IN HOLE W/WIRELINE TO APPROX. 350' AND PERFORATED CASING. 5) RUN TUBING IN HOLE TO APPROX. 350', PUMP APPROX. 100 SKS CLASS A CEMENT (NO BLEND), CIRCULATED CEMENT UP 5.5" CASING TO SURFACE. 6) PULLED TUBING OUT, TIED INTO 5.5 CASING, AND CIRCULATED CEMENT UP BACKSIDE OF 5.5" CASING TO SURFACE. ** 5-20-2016 ** TOPPED OFF CEMENT PLUG IN 5.5" W/ 5 SKS.

* 118 sks total

Perfs:

Top	Bot	Thru	Comments
2725	2727	CSG	
2704	2707	CSG	

Remarks: PERFORATING AND CEMENTING COMPLETED BY ELMORE'S INC, SEDAN, KANSAS. TICKET #: 12207

Plugged through: TBG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

KCC WICHITA
JUN 02 2016
RECEIVED

no
6-9-16