

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-00328-00-00
Spot: NENENW Sec/Twnshp/Rge: 14-34S-4E
4886 feet from S Section Line, 2952 feet from E Section Line
Lease Name: CRAIN Well #: 2
County: COWLEY Total Vertical Depth: 3247 feet

Operator License No.: 3661
Op Name: GROVES, PHIL DBA PHIL GROVES OIL
Address: 811 E MADISON AVE PO BOX 571
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	0		0 SX
SURF	8.63	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2016 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: PHIL GROVES Company: PHIL GROVES OIL Phone: (620) 442-0480

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 05/19/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3216', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 2% CC .5# FLO-SEAL W/100# HULLS & DISPLACED IN CASING. LAYED DOWN TUBING. TAGGED CEMENT PLUG @ 2934'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 250'-251'. RIH W/TBG @ 250', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 240 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE. CEMENT TICKET #51256.

Perfs:

Top	Bot	Thru	Comments
3220	3226		CSG

Remarks: TA LETTERS / COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

KCC WICHITA
JUN 02 2016
RECEIVED

1/8

Form CP-2/3
no
6-9-16