

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23895-00-00
Spot: SESESW Sec/Twnshp/Rge: 2-7S-19W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: FORTUNE RIDGE Well #: 2
County: ROOKS Total Vertical Depth: 3738 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>34055</u>	<u>PROD</u>	<u>5.5</u>	<u>3682</u>		<u>385 SX</u>
Op Name: <u>H & M PETROLEUM CORPORATION</u>	<u>SURF</u>	<u>8.625</u>	<u>218</u>		<u>150 SX</u>
Address: <u>PO BOX 2487</u> <u>COLORADO SPRINGS, CO 80901</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2016 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN MONDERO Company: GREAT PLAINS ENERGY Phone: (785) 475-7245

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 3 hulls and 17 sx gel.
PC at 1455' w/140 sx cement.
Production perforations: 3191' - 3286'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2016 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 75 sx cement w/300 # hulls followed by 17 sx gel, then pumped 115 sx cement to top off 5 1/2" casing. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx gel. Shut in pressure 200 psi.

GPS: 39.46749N -099.40813W

Perfs:

Top	Bot	Thru	Comments
3284	3286		
3211	3213		
3191	3194		

Remarks: SWIFT SERVICES TICKET # 29215

Plugged through: CSG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

MAY 20 2016

KCC WICHITA

MAY 31 2016

RECEIVED

Form CP-2/3

Mo 6-9-16