

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26827-00-00
Spot: W2W2SESW Sec/Twnshp/Rge: 23-15S-17W
660 feet from S Section Line, 1585 feet from W Section Line
Lease Name: K LEIKER Well #: 1
County: ELLIS Total Vertical Depth: 3573 feet

Operator License No.: 33864
Op Name: HABIT PETROLEUM, LLC
Address: 639 280TH AVE PO BOX 243
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1086		425 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/11/2016 12:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC.
Proposal Rcvd. from: GEORGE Company: SHIELDS OIL PRODUCERS INC. Phone: (785) 735-4503

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE
Date/Time Plugging Completed: 05/11/2016 8:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

1st plug @3538 w/50 sx
2nd plug @1175 w/50 sx
3rd plug @500 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: GLOBAL

Plugged through: DP

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

cm

MAY 16 2016

Form CP-2/3

NO
6-9-16