

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-20181-00-00
Spot: NENWNWNW Sec/Twnshp/Rge: 13-31S-10E
5140 feet from S Section Line, 4663 feet from E Section Line
Lease Name: J.W. DURBIN Well #: 10
County: ELK Total Vertical Depth: 1952 feet

Operator License No.: 8736
Op Name: DIXON, JAMES DAVID
Address: 1214 CYCLONE
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1948		35 SX
SURF	7	124		30 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JAMES D. DIXON Company: _____ Phone: (620) 647-3317

Proposed Plugging Method: 1" to bottom, with gel in hole, spot 10 sacks of cement, pull up to 1100-1200 ft, 5 sacks cement, pull up 550 ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 01/27/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Washed well out to TD with 2". Ran 1" to TD gelled hole and spotted 10 sack plug. Pulled 1" and perforated casing at 1000' and 550'. Ran 1" to 1000' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 200 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1940	1944		


RECEIVED
KCC DIST # 3
MAY 31 2016
CHANUTE, KS
DS

Remarks:

Plugged through: TBG

District: 03

Signed



KCC WICHITA

(TECHNICIAN)

JUN 03 2016

RECEIVED

Form CP-2/3

no 6-9-16