

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-30005-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 13-30S-9W  
330 feet from S Section Line, 330 feet from W Section Line  
Lease Name: NICHOLAS B Well #: 1  
County: KINGMAN Total Vertical Depth: 4335 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N MARKET STE 1130  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4335		125 SX
SURF	8.625	239		225 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2016 12:00 PM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: SHANNON RAYBERN Company: \_\_\_\_\_ Phone: (620) 793-2672

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/05/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

BRIDGE AT 780', TRIPPED IN WITH TUBING STARTED DRILLING, WATER RISING TO SURFACE AROUND RIG, SHUT DOWN, CUT HEAD OFF, RAN ONE INCH TUBING INTO 260' IN ANNULUS, PUMEPD 100 SX CEMENT WITH 3% CC. LET SET UP, WENT BACK IN TO BOTTOM WITH TUBING. SET CIBP @ 4100' W/2 SX CEMENT. PERFORATED @ 1400' & 915'. TRIPPED TUBING INTO 1400' SPOTTED 35 SX CEMENT 3% CC, WAIT 2 HOURS TAGGED TOC @ 1300'. TRIPPED TUBING INTO 915' SPOTTED 5- SX CEMENT 100 LBS HULLS, 3% CC., PULLED TUBING TO 250' CIRCULATED TO SURFACE WITH 50 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4245	4251		MISSISSIPPI

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. CASING LEAK PAST 10 YEAR TA.

Plugged through: TBG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAY 23 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*M 6-9-16*

*✓*