

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-21281-00-00  
Spot: NWSESESE Sec/Twnshp/Rge: 20-34S-2E  
336 feet from S Section Line, 416 feet from E Section Line  
Lease Name: ATKINS Well #: 3  
County: SUMNER Total Vertical Depth: 3570 feet

Operator License No.: 32887  
Op Name: ENDEAVOR ENERGY RESOURCES, LP  
Address: 110 N MARIENFELD, STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3530		140 SX
SURF	8.625	138		120 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2016 12:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES, Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/06/2016 3:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

SANDED BACK TO 3475' CAPPED WITH 5 SX. SET CIBP @ 3000', CAPPED WITH 4 SX. PERFORATED 5.5" AT 300'. RAN 325' OF 2.375" TUBING AND PUMPED 130 SX OF CLASS A CEMENT AND CIRCULATE TO SURFACE, PULLED TUBING AND TOPPED OFF WELL WITH AN ADDITIONAL 7 SX. CUT OFF BELOW SURFACE. JOB COMPLETE. TICKET #650203.

Perfs:

Top	Bot	Thru	Comments
3508	3514		TBG
3168	3172		TBG
3058	3060		TBG

Remarks: WELL PLUGGED DUE TO DOCKET #15-CONS-442-CMSC. COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed Daniel Z. Fox  
# \_\_\_\_\_ Received \_\_\_\_\_  
KANSAS CORPORATION COMMISSION (TECHNICIAN)

MAY 25 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*no 6-9-16*

*JK*