

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-21250-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 28-34S-2E
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: CHAPMAN Well #: 2
County: SUMNER Total Vertical Depth: 3594 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3115		
PROD	4.5	3522		180 SX
SURF	8.625	260		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2016 11:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES, Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 04/06/2016 3:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

SET CIBP @ 2975', CAPPED WITH 4 SX. PERFORATED 4.5" AT 325'. RAN 350' OF 2.375" TUBING AND PUMPED 155 SX OF CLASS A CEMENT AND CIRCULATE TO SURFACE, PULLED TUBING AND TOPPED OFF WELL WITH AN ADDITIONAL 5 SX. CUT OFF BELOW SURFACE. JOB COMPLETE. TICKET #650202.

Perfs:

Top	Bot	Thru	Comments
3088	3092	TBG	
3033	3034	TBG	

Remarks: WELL PLUGGED DUE TO DOCKET #15-CONS-442-CMSC. COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 20 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

NO 6-9-16