

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-21333-00-00  
Spot: NENENW Sec/Twnshp/Rge: 28-34S-2E  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: CHAPMAN Well #: 3  
County: SUMNER Total Vertical Depth: 3603 feet

Operator License No.: 32887  
Op Name: ENDEAVOR ENERGY RESOURCES, LP  
Address: 110 N MARIENFELD, STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		50		
PROD	4.5	3250		1603 SX
SURF	8.625	258		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/22/2016 1:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES, Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/06/2016 6:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

SET CIBP @ 3125', CAPPED WITH 4 SX. PERFORATED 4.5" AT 300'. RAN 325' OF 2.375" TUBING AND PUMPED 160 SX OF CLASS A CEMENT AND CIRCULATE TO SURFACE, PULLED TUBING AND TOPPED OFF WELL WITH AN ADDITIONAL 5 SX. CUT OFF BELOW SURFACE. JOB COMPLETE. TICKET #650201.

Perfs:

Top	Bot	Thru	Comments
3183	3203	TBG	
3180	3203	TBG	

Remarks: WELL PLUGGED DUE TO DOCKET #15-CONS-442-CMSC. COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*Daniel B. Fry*  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAY 20 2016  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*no 6-9-16*