

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-11316-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 12-35S-2E
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LAWSON-DEAN Well #: B3
County: SUMNER Total Vertical Depth: 3510 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2620		
PROD	5.5	3510		175 SX
SURF	8.625	198		175 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/04/2016 1:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 04/07/2016 4:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

SET CIBP @ 2500', CAPPED WITH 4 SX. PERFORATED 5.5" AT 300'. RAN 325' OF 2.375" TUBING AND PUMPED 150 SX OF CLASS A CEMENT AND CIRCUALTE TO SURFACE, PULLED TUBING AND TOPPED OFF WELL WITH AN ADDITIONAL 5 SX. CUT OFF BELOW SURFACE. JOB COMPLETE. TICKET #650206.

Perfs:

Top	Bot	Thru	Comments
2575	2580	TBG	

Remarks: WELL PLUGGED DUE TO DOCKET #15-CONS-442-CMSC. COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed _____

Received
KANSAS CORPORATION COMMISSION

MAY 25 2016

CONSERVATION DIVISION
WICHITA, KS

(TECHNICIAN)

Form CP-2/3

NO 9-16
6