

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-21298-00-00
Spot: NWSESE Sec/Twnshp/Rge: 19-34S-2E
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: MCLAUGHLIN Well #: 4
County: SUMNER Total Vertical Depth: 3250 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3249		75 SX
SURF	8.625	257		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2016 7:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES, Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 04/07/2016 11:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

SET CIBP @ 3050', CAPPED WITH 4 SX. PERFORATED 4.5" AT 300'. RAN 325' OF 2.375" TUBING AND PUMPED 165 SX OF CLASS A CEMENT AND CIRCUALTE TO SURFACE, PULLED TUBING AND TOPPED OFF WELL WITH AN ADDITIONAL 10 SX. CUT OFF BELOW SURFACE. JOB COMPLETE. TICKET #650205.

Perfs:

Top	Bot	Thru	Comments
3193	3206	TBG	
3092	3094	TBG	

Remarks: WELL PLUGGED DUE TO DOCKET #15-CONS-442-CMSC. COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed _____

Daniel R. Fox
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 25 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

No 9-16

✓