

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-02844-00-00  
Spot: S2NENWSW Sec/Twnshp/Rge: 31-13S-19W  
2210 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: RIEDEL Well #: 4  
County: ELLIS Total Vertical Depth: 4010 feet

Operator License No.: 31240  
Op Name: ENTERPRISE INC  
Address: 2708 BARCLAY DR  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3924		150 SX
SURF	8.87	250		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/20/2016 9:00 AM  
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC  
Proposal Rcvd. from: STEVE WEILERT Company: ENTERPRISE INC. Phone: (785) 650-1952

Proposed Plugging Method: Ordered 470 sx 60/40 pozmix 4% gel cement and 500 # hulls.  
Casing leaks.  
DV Tool at 1544' w/400 sx cement.  
Perforations: 3521' - 3553', 3548' - 3553', 3835' - 3856'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/20/2016 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Chito's ran in hole with tubing to 3518', rigged to tubing and pumped 150 sx 60/40 pozmix 4% w/300 # hulls mixed in. Pulled tubing to 2050'. Global rigged to tubing, mixed and pumped 250 sx cement w/200 # hulls mixed in to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 40 sx cement to pressure with 400 psi. Shut in pressure 200 psi. Rigged to 8 5/8" surface casing and pumped 5 sx cement. Blew hole in back of head. Casing full.


GPS: 38.87684 -09948118

Remarks: GLOBAL CEMENTING CO TICKET # 2649

Plugged through: TBG

District: 04

Signed



KCC WICHITA

(TECHNICIAN)

CM

MAY 31 2016

RECEIVED

MAY 20 2016

Form CP-2/3

NO  
6-9-16