

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24071-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 20-31S-4E
1696 feet from S Section Line, 2168 feet from E Section Line
Lease Name: BARNARD Well #: 1
County: COWLEY Total Vertical Depth: 3095 feet

Operator License No.: 32679
Op Name: AAS OIL CO., INC.
Address: 2508 EDGEMONT DR STE # 4
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2575		
PROD	4.5	3093		100 SX
SURF	8.625	221		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2016 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: AAS OIL CO Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/20/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2400', DUMP BAILED 4 SXS CEMENT ON TOP PLUG.
RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 250'-251'. SDON, 5-20-2016,
RIH W/TBG @ 272', CONSOLIDATED OILWELL SERVICES ESTABLISHED
CIRCULATION, MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL 2% CC TO
SURFACE. CEMENT CIRCULATED. CEMENT TICKET #51257.

Perfs:

Top	Bot	Thru	Comments
2427	2433		CSG

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

KCC WICHITA
JUN 02 2016
RECEIVED

Form CP-2/3

Handwritten: No 6-9-16

Handwritten: JK