

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Palomino Petroleum  
Complete Address 304 Insurance Bldg., Wichita, Kansas 67202  
Lease Name Hoffman Well No. 1  
Location C NE NW Sec. 36 Twp. 24 Rge. 22 (E) (W)  
County Hodgeman Total Depth 4765'  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated       
Plugging Contractor Glenn & Smith  
Address Ellinwood, Kansas License No. 396  
Operation Completed: Hour 5:00PM Day 21 Month 3 Year 1973

The above well was plugged as follows:

8 5/8" to 331' circulated w/ cement. 5 1/2" to 4760' cemented.  
Top perforations 4653' Plug bottom w/sand & 5 sacks cement .  
Top of cement 4175' Mud 4175' to 800'  
Spotted 80 sacks cement 800' to 500' Mud 500' to 330'  
Spotted 30 sacks cement 330' to 230' Mud 230' to 45'  
Plug, Hulls & 15 sacks cement 45' to 0'. Allied Pump Truck.  
Pulled 2700' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves  
Well Plugging Supervisor

INVOICED

DATE 3/29/73  
INV. NO. 7181-W