

yc
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kenneth Rupp

Complete Address: 427 Union Center, Wichita, Kansas

Lease Name Jetmore Airport Well No. 1

Location SW SW NE Sec. 7 Twp. 24 Rge. (E) (W) 23

County Hodgeman Total Depth 4871'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Red Tiger Drilling Company

Address: Wichita, Kansas License No.

Operation Completed: Hour 1130AM Day 12 Month 2 Year 64

The Above well was plugged as follows:

8 5/8"-278' Circulated w/cement.

Mud 4871' to 700' Spotted 25 Sax.cement 700' to 625'

Mud 625' to 275' Spotted 25 Sax.cement 275' to 200'

Mud 200' to 40' Plug,Hulls,15 Sax.cement 40' to 0

Sun Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 2/14/64

INV. NO. 8642-W