

KANSAS

X STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name O.A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas

Lease Name Jetmore Airport Well No. 1

Location C S/2 SE SW Sec. 7 Twp. 24 Rge. 23 XX (W)

County Hodgeman Total Depth 4890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Gabbert & Jones

Address: 830 Sutton Place, Wichita, Kansas License No.

Operation Completed: Hour 7:00PM Day 16 Month 5 Year 1968

The Above well was plugged as follows:

8 5/8" to 301' circulated w/ cement. Mud 4890' to 550'

Spotted 25 sacks cement 550' to 460' Mud 460' to 300'

Spotted 20 sacks cement 300' to 240' Mud 240' to 40'

Plug, Halls & 10 sacks cement 40' to 0'

Halliburton Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/20/68
INV. NO. 7976-u

Signed: Edgar J. Eves
Well Plugging Supervisor