

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-19015-00-02 ⁰¹ 15-095-19015-0001
Spot: NENE Sec/Twnshp/Rge: 33-29S-6W
660 feet from N Section Line, 660 feet from E Section Line
Lease/Unit Name: ROBERTSON A Well Number: 2
County: KINGMAN Total Vertical Depth: 4502 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 78020
WICHITA, KS 67278

Conductor Pipe: Size feet: 8 1/46.32
Surface Casing: Size 8.625 feet: 264 200 SX CMT
Production: Size 5.5 feet: 4499 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/29/2001 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone:

Proposed
Plugging
Method:

Perfs 4133'-42'. Sand to 4080 and 5sxs. 35sxs-1050'. 35sxs-600'. Circulated 210'-0'.

Plugging Proposal Received By: STEVE VANGIESON
Date/Time Plugging Completed: 11/29/2001 11:00 AM

WitnessType: Plugging Operations Partially Witnessed
KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were covered with sand from 4200'-4061' and capped w/5sxs of cement. The casing was recovered from 1631' and pulled from the wellbore, tubing was run to 1050', where 35sxs of cement was spotted. The tubing was pulled to 600' where 35sxs of cement was spotted. The tubing was pulled to 310', where cement was circulated to surface. The remaining tubing was pulled and the cement was topped off.

RECEIVED
KCC DISTRICT #2


DEC 07 2001
12-07-01
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 4% GEL # 8624

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-10-01

WV. NO. 2002061045