

2 040299

FEB 3 1987 15-095-19025-0000  
API NUMBER 15-095-19025-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

else, SEC. 33, T 29 S, R 6 W/E

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Replow Well # 3

Operator: Pckrell Drilg. Co

County Kingman 146.25

Name & Address 110 N. Market Sub 205

Well Total Depth 4500 feet

Wichita KS. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clark Corp. License Number \_\_\_\_\_

Address Medicine Lodge Ks

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Elmo

(company name) Clark Corp (phone) 5105

were: Sand to 4400', 5 sks

3hull, 15gal, Plug, 100sx, Plug, 25sks

Plugging Proposal Received by Dist 2 (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 1110 Day: 3 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT Clark Corp. rigged up over the hole and dumped sand down the 5 1/2" casing to 4400' and capped with 5 sks of cement thru dump trailer. The 5 1/2" casing was shot off and recovered from 2550'. The top was squeezed plugged by pumping 3 sks of hull, 15 sks of gel, a wiper plug, 100 sks of cement, a wiper plug, and 25 sks of cement

Remarks: Allied 40/40 Poz #1571 MX 600\* SI 350#

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-16-87

INV. NO. 16126 W

FEB 12 1987 Signed

CONSERVATION DIVISION  
Wichita, Kansas

02-12-87

St. V. Sen (TECHNICIAN)