

2 010155

DEC 31 1986

15-095-30017-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-095-30017-0000 API NUMBER 15- N/A

TECHNICIAN'S PLUGGING REPORT

_____ feet from S section line
_____ feet from E section line

Operator License # 5123

Lease Name Pieplow Well # 4

Operator: Pickrell Drilling Co Inc.
Name & Address 110 N. Market St 205
Wichita Ks 67202
(316) 262-8427

County Kingman 108.88
Well Total Depth 3350 (BTD 3314) ^{FLGAT} feet

Conductor Pipe: Size 4 1/2 feet 3343 ¹⁰⁰ 5x

Surface Casing: Size 8 5/8 feet 202 ¹⁵⁵ 5x

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Perf 3280-384

Plugging Contractor Clarke Corp License Number 5105

Address 107 W Fowler, Medicine Lodge, Ks 67104

Company to plug at: Hour: 10:AM Day: 31 Month: 12 Year: 19 86

Plugging proposal received from Don Amiller

(company name) Clarke Corp. (phone) (316) 886-5665

were: Plug Back with sand 3200'. Use dump bailer to
dump 4 5x cement on sand. Cut off & recover pipe.
Tie into surface & pump 3 5x Halls - 15 5x gel - 8 5/8 wiper
plug - 100 5x cmt 8 5/8 wiper plug - 25 5x cmt

Plugging Proposal Received by Warren Kirkpatrick
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:00A Day: 31 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT Sand To 3200' + 4 5x cement -

Shot off & galled 2750 of 4 1/2 Pump 3 hells - 15 gel -
and 100 5x cement - add plug and 25 5x cement

RECD
01-12-87
STATE CORPORATION COMMISSION
JAN 19 1987

Remarks: Allied 60/40 3% 600# gel - 400# 5L.
(If additional description is necessary, use BACK of this form.)

INVOLCED

DATE 1-13-87

INV. NO. 15891

Signed Warren Kirkpatrick
(TECHNICIAN)