

2 040262

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-20611 0000

C- SE14, SEC. 16, T. 29 S, R. 8 W#

1320 feet from N/S section line

3960 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7062

Lease Name Clouse Well # 1

Operator: Keener Oil Co.

County Kingman 135.3/6

Name & Address 320 S. Boston St #406

Well Total Depth 4165 feet

Tulsa OK 74103

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) _____

were: _____

4 1/2 4155 Sand to 4100' & 4 sks

O.H. 4155-65 3 hull, 15 gel, 115 sk

STATE CORPORATION COMMISSION
RCWD

04-25-86 APR 25 1986

Plugging Proposal Received by Stan No CONSERVATION DIVISION
(TECHNICIAN) Wichita, Kansas

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 1100 Day: 15 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT Sand was dumped inside the 4 1/2"

casing to 4100' to fill open hole, and capped with
4 sacks of cement, spotted with the dump trailer. The
4 1/2" casing was shot off and recovered from 2893'. The
top was squeeze plugged thru the 8 5/8" casing by pumping
3 sks of hulls, 15 sks of gel, 90 sks of cement, and wycis plug,

Remarks: and 20 sacks of cement. MX350 SI 200
(If additional description is necessary, use BACK of this form.)

INVOICED

(If you did not observe this plugging.

Allied Cement Signed Stan No
(TECHNICIAN)

DATE APR 25 1986

INV. NO. 13537

2327 W